(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Chamundi Brand cement alone to be used.

Detailed estimate for constructing a tunnel and a causeway at Davangere-Sulekere Road.

Sl. No.	Details of work	Unit	Quantity	Rate	Rates tendered	
					In words	In figures
				Rs. a. p.	Rs. a. p.	Rs. a. p.
1	Earthwork excavation	C.yd.	67	0 3 0		
2	Concrete in surki mortar ..	C.ft.	600	0 4 0		
3	Size stone in mortar	,,	1,803	0 4 0		
4	R. C. concret slabs of 8″ thick (1 : 2 : 4)	,,	330	1 12 0		
5	Bearing slabs of cement concrete (1 : 3 : 6)	,,	75	0 10 0		
6	Wearing coat (1 : 2 : 4) ..	,,	58	0 10 0		
7	Cement pointing	Sqr.	6.72	4 0 0		
	Causeway.					
1	Earthwork excavation	C.yd.	82	0 3 0		
2	Concrete in surki mortar ..	C.ft.	1,386	0 4 0		
3	Size stone in mortar	,,	1,748	0 4 0		
4	Cement pointing	Sqr.	11.66	4 0 0		
5	Rough stone filling	C.yd.	121	1 8 0		
6	Cement concrete slab	C.ft.	274	0 10 0		
	Constructing sidewall.					
7	(*a*) Earthwork excavation ..	C.yd.	..	..		
	(*b*) Rough stone dry wall ..	,,	..	..		
	Temporary Deviation works, etc.					
8	(*a*) Earthwork excavation ..	,,	..	..		
	(*b*) Earthwork filling in pits ..	,,	..	..		
	(*c*) Forming road way by 3″ cutting or banking	S.yd.	..	..		
	(*d*) Clearing Jungle	,,	..	..		
	(*e*) Barricading the road both ways danger-lights and watchman	Month	..	..		
9	Bailing out water	..	..	..		

S. RAMASWAMY,
Executive Engineer.

MEDICAL DEPARTMENT

KRISHNARAJENRDA HOSPITAL MYSORE.

Abstract Notice dated 7th February 1939.

Sealed tenders for the supply of Bedding and Clothing required for the use of Krishnarajendra Hospital for the year 1939 will be received by the undersigned on Saturday the 11th March 1939 at 11 A.M. at the Krishnarajendra Hospital, Mysore.

For further particulars, *vide Mysore Gazette* of 16th February 1939, Part VI, pages 317-318.

J. F. ROBINSON,
Durbar Surgeon and Medical Officer.